

**PCCO #056**

Hueber-Breuer Construction Co, Inc.
148 Berwyn Ave.
Syracuse, New York 13210
Phone: (315) 476-7917
Fax: (315) 476-7990

Project: 16-474 USL - 505 Walnut Ave Apartments (USL)
505 Walnut Avenue
Syracuse, New York 13210

Prime Contract Change Order #056: PCCO 56 High Speed Overhead Door

TO:	Southside Genesee Associates, LLC 3 East Stow Road, Suite 260 Marlton , New Jersey 08053	FROM:	Hueber-Breuer Construction Co., Inc. 148 Berwyn Avenue, PO Box 515 Syracuse New York 13205
DATE:	3/ 09 /2018	CREATED BY:	Lisa Weaver (Hueber-Breuer Construction Co., Inc.)
SCHEDULE IMPACT:		EXECUTED:	No
CONTRACT FOR:	1:505 Walnut Ave (USL) Prime Contract	TOTAL AMOUNT:	\$ 21,637.75

DESCRIPTION:

CE #090 - High Speed Overhead Coiling Garage Door

Furnish and install high speed overhead coiling garage door with 4 rows of vision panels. GMP included standard overhead coiling door. Cost of upgrade is the difference between the two coiling doors. Door will not be ordered until a signed change order is received.

Cost = \$21,110.00
Fee = \$527.75
Total = \$21,637.75

ATTACHMENTS:
[PCCO 56 Hish Speed Overhead Door.pdf](#)

The original (Contract Sum)	\$ 34,846,056.00
Net change by previously authorized Change Orders	\$ 367,935.64
The contract sum prior to this Change Order was	\$ 35,213,991.64
The contract sum will be increased by this Change Order in the amount of	\$ 21,637.75
The new contract sum including this Change Order will be	\$ 35,235,629.39
The contract time will by this Change Order by	

David McHenry, Erdy McHenry
Architecture, LLC

Southside Genesee Associates, LLC
3 East Stow Road, Suite 260
Marlton New Jersey 08053

Hueber-Breuer Construction Co., Inc.
148 Berwyn Avenue, PO Box 515
Syracuse New York 13205

DocuSigned by:
David McHenry 4/13/2018

DocuSigned by:
Michael Cassarino 3/12/2018

DocuSigned by:
Derek Heath 3/9/2018

SIGNATURE

DATE

SIGNATURE

DATE

SIGNATURE

DATE



MULLEN
INDUSTRIAL
HANDLING
CORP.

6245 Fly Road - P.O. Box 246 • East Syracuse, NY 13057 • Phone 315-437-3386 • Toll Free 800-836-0485 • Fax 315-437-6044

Derek Heath
Hueber-Breuer Construction Co. Inc.
148 Berwyn Avenue
Syracuse, NY 13205-0515
315-476-7917
315-476-7990 (Fax)

Thursday, March 1, 2018

Reference Job:
Quote# 68696-JK R4
High Speed Garage Door
USL Walnut

<u>Product Description</u>	<u>Qty</u>	<u>Unit Price</u>	<u>Extended Price</u>
Garage Door - ASI-Marathon High Speed Door	1	\$36,960.00	\$36,960.00
			-15,850.00
			<u>\$21,110.00</u>



109LP High Performance Roll-Up

- Door Opening Size: 24' Wide x 8' High

Operation:

- **Dual Speed Operation** : Up to 42"/Sec Open; 21"/Sec Close.
- 3-HP Direct Drive Operator is available in 230V or 460V 3 Phase NEMA-4.
- High Cycle Rated Door System.

Curtain:

- Aluminum insulated slats with Heavy Duty Clear Anodized finish on exterior, Orange or Gray PVC on the interior - no metal-on-metal contact. The curtain withstands heavy exterior windloads and pressures. Electric reversing soft bottom edge.

Controls:

- Variable Frequency Drive (VFD) system for soft start/stop operation.
- Programmable Control Logic (PLC) for easy system interface.

Control Features:

- (1) three button station (open/close/e-stop) mounted on the control box.
- (2) sets of send/receive reversing photoeyes.
- Floor accessible emergency manual chain hoist device.

Included Options:

- Gray insulated slats
- Bottom bar stiffener req'd
- Galvanized side covers
- Galvanized shroud
- Prep For Activation Controls by Others
- **1) Set of (4) High Vision Panels** - Full width across the door (as per picture above), each vision pane is 17" long. *Add \$660.00 for additional sets

- **Estimated Lead Time:** 8 Weeks to ship ARO & Approvals, allow additional week for delivery time.

Freight and Handling
Installation
Tax
Total

Included
Included
Add*
\$36,960.00