

HRP Associates, Inc.

Creating the Right Solutions Together

November 29, 2005

Mr. Peter Hill
Permitting, Enforcement and Remediation Division
Connecticut Department of Environmental Protection
79 Elm Street
Hartford, CT 06106

RE: SEMI-ANNUAL GROUNDWATER MONITORING AND SUBSURFACE INVESTIGATION REPORT, FORMER TORRINGTON COMPANY, BOOTH STREET, NEW BRITAIN, CONNECTICUT (HRP #ING0036.OM)


Dear Mr. Sordi:


Attached for your review is the report describing the August 2005 groundwater monitoring event and the installation of additional wells at the above-referenced site.


If you have any questions or require any additional information, please contact HRP at (860) 793-6899.

Sincerely,

HRP ASSOCIATES, INC.


Robin C. Fox
Project Geologist


Michael S. Swaim
Senior Project Geologist


Robert H. Leach
Chief Operating Officer

rcf
Attachments

cc: David Sordi, Ingersoll-Rand
Jack Healy, ERM

CONNECTICUT

167 New Britain Avenue
Plainville, CT 06062
800-246-9021
860-793-6899
FAX 860-793-6871

NEW YORK

100 Saratoga Village Blvd
Suite 27
Malta, NY 12020
888-823-6427
518-899-3011
FAX 518-899-8129

PENNSYLVANIA

4811 Jonestown Road
Suite 235
Harrisburg, PA 17109
866-232-9824
717-920-1350
FAX 717-920-1353

SOUTH CAROLINA

7001 Pelham Road
Suite J
Greenville, SC 29615
800-752-3922
864-289-0311
FAX 864-281-9846

www.hrpassociates.com

Due Diligence
Site Investigations
Brownfields Redevelopment
Remedial/Corrective Action
Civil Engineering
Land Surveying
Site Planning
Environmental Permitting
Hazardous Waste Management
Air Quality & Pollution Control
Water & Wastewater Management
Health & Safety
Environmental Management Systems

**AUGUST 2005
SEMI-ANNUAL GROUNDWATER
MONITORING AND SUBSURFACE
INVESTIGATION REPORT**

**FORMER TORRINGTON COMPANY
BOOTH STREET
NEW BRITAIN, CONNECTICUT**

HRP #ING0036.OM

November 29, 2005

Prepared for:


Ingersoll-Rand
70 North Street
Torrington, CT 06790

Prepared by:


HRP Associates, Inc.
Engineering & Geology
167 New Britain Avenue
Plainville, CT 06062



Robin C. Fox
Project Geologist



Michael S. Swaim
Senior Project Geologist



Robert H. Leach
Chief Operating Officer

TABLE OF CONTENTS

<i>Section</i>	<i>Page</i>
1.0 BACKGROUND	1
2.0 SITE GEOLOGY	3
3.0 INSTALLATION OF ADDITIONAL MONITORING WELLS AND SOIL BORINGS	3
3.1 Methods of Installation	4
3.2 Description of Soils and Field Screening Results	4
3.3 Laboratory Analysis of Soil	5
3.4 Comparison With CT DEP Remediation Standard Regulations (RSR)	6
4.0 NON-AQUEOUS PHASE LIQUID MONITORING	7
5.0 GROUNDWATER MONITORING	8
5.1 Sampling Methods	8
5.2 Groundwater Flow	9
5.3 Laboratory Results	9
5.4 Significant Hazard Notification Evaluation	14
6.0 CONCLUSIONS	14
7.0 SCHEDULE	16

LIST OF TABLES

- 1 Summary of Laboratory Results for Soil
- 2 Groundwater Elevation Data
- 3 Summary of Groundwater Analytical Data – ETPH and VOCs
- 4 Summary of Metals in Groundwater
- 5 Historical Detections of Halogenated VOCs in Groundwater
- 6 Summary of Post Remediation ETPH Concentrations in Ground Water
- 7 Historical Detections of Metals and PCBs in Groundwater
 - a. Arsenic
 - b. Cadmium
 - c. Lead

LIST OF FIGURES

- 1 Site Plan Depicting Testing Locations
- 2 RMW-2 NAPL Thickness and Ground Water Elevations
- 3 Groundwater Flow Map (overburden)
- 4 Groundwater Flow Map (bedrock)
- 5 TCA in Ground Water
- 6 11DCE in Ground Water
- 7 Summary of HVOCs in Well RMW-8R
- 8 Summary of HVOCs in Well RMW-11
- 9 Summary of HVOCs in Well RMW-13

LIST OF APPENDICES

- A Drilling Logs and Well Completion Diagrams
- B Field Data Sheets
- C Modified Low-Flow Sampling Data Sheet
- D Complete Laboratory Reports